

RENLITA DOORS NORTH AMERICA LLC

THERMAL PERFORMANCE TEST REPORT

SCOPE OF WORK

S-500 / S-1000 / S-2000 / S-3000 GARAGE DOORS

REPORT NUMBER

L0326.01-116-46 R0

TEST DATE

06/11/20

ISSUE DATE

06/30/20

RECORD RETENTION END DATE

06/11/25


PAGES

27

DOCUMENT CONTROL NUMBER

RTTDS-R-AMER-Test-2822(a) (07/07/18)

©2017 INTERTEK



TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

REPORT ISSUED TO

RENLITA DOORS NORTH AMERICA LLC

200 East 1st Street

Bonham, Texas 75418

SECTION 1

SCOPE

SERIES/MODEL: S-500 / S-1000 / S-2000 / S-3000 Garage Doors

TYPE: GARAGE DOOR

Intertek Building & Construction (Intertek B&C) was contracted by Renlita Doors North America LLC to evaluate the thermal performance per NFRC 102-2017. The purpose of this testing was to evaluate the U-Factor performance. Results obtained are tested values and were secured by using the designated test method. Testing was conducted at Intertek B&C test facility in York, Pennsylvania. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

SECTION 2

SUMMARY OF TEST RESULTS

Standardized U-factor (Ust) (Area-weighted): 0.56 Btu/hr-ft²·F (A.W. Method)

For INTERTEK B&C:

COMPLETED BY	Shon W. Einsig
TITLE	Technician Team Leader, IIRC
SIGNATURE	
DATE	06/30/20

SWE:kmm

REVIEWED BY	Ryan P. Moser
TITLE	Senior Technician
SIGNATURE	
DATE	06/30/20

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 3

TEST SPECIMEN SUMMARY

SERIES/MODEL	S-500 / S-1000 / S-2000 / S-3000 Garage Doors
TYPE	Garage Door
OVERALL SIZE	83" x 82-3/8" (2108 mm x 2092 mm)
NFRC STANDARD SIZE	84" x 84" (2134 mm wide x 2134 mm high)
TEST SAMPLE SUBMITTED BY	Client
TEST SAMPLE SUBMITTED FOR	Validation for Initial Certification (Production Line Unit) & Plant Qualification

SECTION 4

TEST METHOD

The specimens were evaluated in accordance with the following:

NFRC 102-2017, Procedure for Measuring the Steady-State Thermal Transmittance of Fenestration Systems

SECTION 5

MATERIAL SOURCE/INSTALLATION

The test specimen was provided by the client. Representative samples of the test specimen will be retained by Intertek B&C for a minimum of two and half years from the submittal date to the Inspection Agency and no more than 5 years from the test date.

Test Chamber Installation

The test sample was installed in a vertical orientation, the exterior of the specimen was exposed to the cold side.

SECTION 6

LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Ryan P. Moser	Intertek B&C
Shon W. Einsig	Intertek B&C

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 7

TEST SAMPLE DESCRIPTION

Panel 1

MATERIAL	AU (0.07"): Aluminum with Thermal Improvement - All Members		
SIZE	83" x 59-1/2"		
DAYLIGHT OPENING	38-1/2" x 18-1/2" (x2)	GLAZING METHOD	Exterior
EXTERIOR COLOR	Gray	EXTERIOR FINISH	Anodized
INTERIOR COLOR	Black	INTERIOR FINISH	Paint
CORNER JOINERY	Mitered / Screws / Welds / Sealed		

Panel 2

MATERIAL	AU (0.07"): Aluminum with Thermal Improvement - All Members		
SIZE	83" x 22-3/4"		
DAYLIGHT OPENING	38-1/2" x 18-1/2" (x2)	GLAZING METHOD	Exterior
EXTERIOR COLOR	Gray	EXTERIOR FINISH	Anodized
INTERIOR COLOR	Black	INTERIOR FINISH	Paint
CORNER JOINERY	Mitered / Screws / Welds / Sealed		

Glazing Information

LAYER 1	1/4"	SolarBan 60 (e=0.035*, #2)	
GAP 1	0.50"	A1-D: Aluminum Spacer	100% Air*
LAYER 2	1/4"	Clear	
GAS FILL METHOD	N/A*		

**Stated per Client/Manufacturer*

N/A Non-Applicable

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 7 (CONTINUED)

TEST SAMPLE DESCRIPTION (CONTINUED)

Weatherstripping

DESCRIPTION	QUANTITY	LOCATION
(1-1/4" dia.) Custom rubber rigid flexible hollow bulb gasket	1 Row	Bottom of bottom panel
(1" dia.) Flexible hollow foam gasket	1 Row	Top of bottom panel, bottom of top panel
(1/2" dia.) Flexible hollow vinyl gasket	1 Row	Top of top panel

Hardware

DESCRIPTION	QUANTITY	LOCATION
(1" dia.) Steel lifting/cable rod	2	Bottom panel stiles
Mortise hinge	3 Sets	Top / bottom panels joint
Steel lifting bracket	2	Top panel ends

Drainage

DRAINAGE METHOD	SIZE	QUANTITY	LOCATION
Diameter weephole	(1/4" dia.)	8	Four per each panel bottom

TEST REPORT FOR RNLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 8

THERMAL TRANSMITTANCE (U-FACTOR): MEASURED TEST DATA

Heat Flows

1. Total Measured Input into Metering Box (Qtotal)	2236.54 Btu/hr
2. Surround Panel Heat Flow (Qsp)	80.76 Btu/hr
3. Surround Panel Thickness	4.00 inches
4. Surround Panel Conductance	0.0476 Btu/hr·ft ² ·F
5. Metering Box Wall Heat Flow (Qmb)	12.89 Btu/hr
6. EMF vs Heat Flow Equation (equivalent information)	0.0117*EMF + -0.044
7. Flanking Loss Heat Flow (Qfl)	16.81 Btu/hr
8. Net Specimen Heat Loss (Qs)	2126.08 Btu/hr

Areas

1. Test Specimen Projected Area (As)	49.22 ft ²
2. Test Specimen Interior Total (3-D) Surface Area (Ah)	57.01 ft ²
3. Test Specimen Exterior Total (3-D) Surface Area (Ac)	45.77 ft ²
4. Metering Box Opening Area (Amb)	75.11 ft ²
5. Metering Box Baffle Area (Ab1)	70.84 ft ²
6. Surround Panel Interior Exposed Area (Asp)	25.89 ft ²

Test Conditions

1. Average Metering Room Air Temperature (th)	69.80 F
2. Average Cold Side Air Temperature (tc)	-0.41 F
3. Average Guard/Environmental Air Temperature	71.24 F
4. Metering Room Average Relative Humidity	7.39 %
5. Metering Room Maximum Relative Humidity	8.07 %
6. Metering Room Minimum Relative Humidity	6.83 %
7. Measured Cold Side Wind Velocity (Perpendicular Flow)	12.66 mph
8. Measured Warm Side Wind Velocity (Parallel Flow)	N/A mph
9. Measured Static Pressure Difference Across Test Specimen	0.00" ± 0.04" H ₂ O

Average Surface Temperatures

1. Metering Room Surround Panel	65.51 F
2. Cold Side Surround Panel	0.01 F

Results

1. Thermal Transmittance of Test Specimen (Us)	0.62 Btu/hr·ft ² ·F
2. Standardized Thermal Transmittance of Test Specimen (Ust)	0.56 Btu/hr·ft ² ·F

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 9

THERMAL TRANSMITTANCE (U-FACTOR): CALCULATED TEST DATA

Area-Weighted Method Results

1. Area-Weighted Warm Side Surface Temperature (t1)	49.92 F
2. Area-Weighted Cold Side Surface Temperature (t2)	9.74 F
3. Measured Warm Side Surface Conductance (hh)	1.88 Btu/hr·ft ² ·F
4. Measured Cold Side Surface Conductance (hc)	4.58 Btu/hr·ft ² ·F
5. Standardized Warm Side Surface Conductance (hsth)	1.36 Btu/hr·ft ² ·F
6. Standardized Cold Side Surface Conductance (hstc)	5.28 Btu/hr·ft ² ·F
7. Standardized Thermal Transmittance (Ust)	0.56 Btu/hr·ft ² ·F

SECTION 10

TEST DURATION

1. The environmental systems were started at 11:38 hours, 06/10/20.
2. The test parameters were considered stable for two consecutive four hour test periods from 22:10 hours, 06/10/20 to 06:10 hours, 06/11/20.
3. The thermal performance test results were derived from 02:10 hours, 06/11/20 to 06:10 hours, 06/11/20.

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 11

GLAZING DEFLECTION

	PANEL 1	PANEL 2
EDGE GAP WIDTH	0.50" / 0.50" / 0.50" / 0.50"	0.50" / 0.50"
ESTIMATED CENTER GAP WIDTH upon receipt of specimen in laboratory (after stabilization)	0.50" / 0.50" / 0.50" / 0.50"	0.50" / 0.50"
CENTER GAP WIDTH at laboratory ambient conditions on day of testing	0.50" / 0.50" / 0.50" / 0.50"	0.50" / 0.50"
CENTER GAP WIDTH at test conditions	0.47" / 0.47" / 0.47" / 0.47"	0.47" / 0.47"

Glass collapse determined using a digital glass and air space meter

The sample was inspected for the formation of frost or condensation, which may influence the surface temperature measurements. The sample showed no evidence of condensation/frost at the conclusion of the test.

“This test method does not include procedures to determine the heat flow due to either air movement through the specimen or solar radiation effects. As a consequence, the thermal transmittance results obtained do not reflect performances which are expected from field installations due to not accounting for solar radiation, air leakage effects, and the thermal bridge effects that have the potential to occur due to the specific design and construction of the fenestration system opening. The latter can only be determined by in-situ measurements. Therefore, it is important to recognize that the thermal transmittance results obtained from this test method are for ideal laboratory conditions and should only be used for fenestration product comparisons and as input to thermal performance analyses which also include solar, air leakage and thermal bridge effects.”

Required annual calibrations for the Intertek B&C, 'thermal test chamber' (ICN 000001) in York, Pennsylvania were last conducted in April 2020 in accordance with Intertek B&C calibration procedure. A CTS Calibration verification was performed March 2020. A Metering Box Wall Transducer and Surround Panel Flanking Loss Characterization was performed April 2020.

The reported Standardized Thermal Transmittance (Ust) was determined using CTS Method, per Section 9.2(A) of NFRC 102.

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 12

CTS CALIBRATION DATA

1. CTS Test Date	08/11/18
2. CTS Size	43.06 ft ²
3. CTS Glass/Core Conductance	0.42 Btu/hr·ft ² ·F
4. Warm Side Air Temperature	69.79 F
5. Cold Side Air Temperature	-0.40 F
6. Warm Side Average Surface Temperature	54.30 F
7. Cold Side Average Surface Temperature	3.52 F
8. Convection Coefficient (Kc)	0.34 Btu/(hr·ft ² ·F ^{1.25})
9. Measured Cold Side Surface Conductance (hc)	5.50 Btu/hr·ft ² ·F
10. Measured Thermal Transmittance	0.31 Btu/hr·ft ² ·F

ANSI/NCSL Z540-2-1997 type B uncertainty for this test was 1.54%.

"Ratings included in this report are for submittal to an NFRC licensed IA for certification purposes and are not meant to be used for labeling purposes. Only those options identified on a valid Certificate of Authorization (CA) are to be used for labeling purposes."

The direction of heat transfer was from the interior (warm side) to the exterior (cold side) of the specimen. The ratings were rounded in accordance to NFRC 601, NFRC Unit and Measurement Policy. The data acquisition frequency is 5 minutes.


TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 13

SURROUND PANEL WIRING DIAGRAM




TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 14

BAFFLE WIRING DIAGRAM



TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC


Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 15

SUBMITTAL FORM AND DRAWINGS

The test specimen drawings which follow have been reviewed by Intertek B&C and are representative of the test specimen(s) reported herein. Test specimen construction was verified by Intertek B&C per the drawings included in this report. Any deviations are documented herein or on the drawings.



NOTE:
VIEW IS FROM EXTERIOR


 Report #: L0326.01-116-46
 Date: 06/11/2020
 Verified by: *[Signature]*


UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES.

TOLERANCES

.X=±.050
.XX=±.015
.XXX=±.005

ANGULAR ±.5°

DRAWN DSF	12/19/2016	RENLITA	
CHECKED		TITLE	
QA		S-2000 ENERGY TESTING	
MFG		SIZE	DWG NO
APPROVED		C	2K-ENERGY
		SCALE 1:1	REV 1
			SHEET 1 OF 3



HARDWARE NOT MODELED (TYP)

SECTION A-A

SECTION C-C

SECTION B-B


 Report #: L0326.01-116-46
 Date: 06/11/2020
 Verified by: *[Signature]*

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES.


TOLERANCES

.X=±.050
.XX=±.015
.XXX=±.005


ANGULAR ±.5°

DRAWN	DSF	12/19/2016	RENLITA	
CHECKED			TITLE	
QA			S-2000 ENERGY TESTING	
MFG			SIZE	DWG NO
APPROVED			C	2K-ENERGY
			SCALE 1:1	REV 1
				SHEET 2 OF 3


Report #: L0326.01-116-46
 Date: 06/11/2020
 Verified by: *[Signature]*




SECTION D-D



SECTION F-F



SECTION E-E



SECTION G-G

UNLESS OTHERWISE SPECIFIED
 DIMENSIONS ARE IN INCHES.


 TOLERANCES
 .X=±.050
 .XX=±.015
 .XXX=±.005
 ANGULAR ±.5°

DRAWN	12/19/2016	RENLITA	
DSF		TITLE	
CHECKED		S-2000 ENERGY TESTING	
QA		SIZE	DWG NO
MFG		C	2K-ENERGY
APPROVED		SCALE 1:1	REV 1
			SHEET 3 OF 3


2"
CONSTANT

16" O.C. SPACING

4"
MAY VARY



TYP. GLAZING DETAIL



DETAIL FOR THERMAL MODELING OF
HELIMA ALUMINUM SPACER (A1-D)

 Total Quality. Assured.	Report #:	L0326.01-116-46
	Date:	06/11/2020
	Verified by:	<i>Shon W. Conroy</i>


TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 16

THERMOCOUPLE LOCATION DIAGRAM AND TEMPERATURE CHART



TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 16 CONT.

THERMOCOUPLE LOCATION DIAGRAM AND TEMPERATURE CHART

TEMPERATURE CHART - (F)		
THERMOCOUPLE	EXTERIOR	INTERIOR
1	19.45	39.50
2	18.99	40.32
3	35.47	50.79
4	17.62	45.57
5	32.56	51.35
6	18.87	47.85
7	19.24	46.53
8	34.60	52.13
9	14.05	44.64
10	32.07	50.75
11	18.46	41.44
12	19.71	40.87
13	21.13	44.32
14	19.71	43.15
15	40.80	58.66
16	20.98	48.47
17	32.58	56.03
18	34.12	62.74
19	31.68	60.73
20	10.56	34.39
21	4.33	51.82
22	4.43	52.53
23	13.01	42.61
24	4.50	52.55
25	3.92	51.53
26	10.56	43.16
27	5.53	61.60
28	3.92	60.25
29	17.29	42.56
AVERAGE	19.32	48.93

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 17
PHOTOGRAPHS



PHOTOGRAPH 1 - Interior of garage door installed

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 17 CONT.
PHOTOGRAPHS



PHOTOGRAPH 2 - Exterior of garage door installed

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 17 CONT.

PHOTOGRAPHS



PHOTOGRAPH 3 - Interior bottom of garage door installed



PHOTOGRAPH 4 - Interior bottom left of garage door installed

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 17 CONT.

PHOTOGRAPHS



PHOTOGRAPH 5 - Interior top of garage door installed



PHOTOGRAPH 6 - Interior top left of garage door installed

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 17 CONT.

PHOTOGRAPHS



PHOTOGRAPH 7 - Interior bottom left of garage door installed

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 17 CONT.
PHOTOGRAPHS



PHOTOGRAPH 8 - Interior bottom right of garage door installed

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 17 CONT.

PHOTOGRAPHS



PHOTOGRAPH 9 - Interior top right of garage door installed

TEST REPORT FOR RENLITA DOORS NORTH AMERICA LLC

Report No.: L0326.01-116-46 R0

Date: 06/30/20

SECTION 18

REVISION LOG

REVISION #	DATE	PAGES	REVISION
.01 R0	06/30/20	N/A	Original Report Issue